

Figure AIII-38: Dual Biopolymer (DPS): with Tank, Bag and Wattles.

Active Treatment of Turbid Water Utilizing a Liquid Dual Polymer System with
Pre-Filtration and Sand Filtration

WHAT IS ITS PURPOSE?

To clean construction storm water from a pond using an active system prior to discharge into a regulated and/or high quality water body.

PLEASE NOTE: These systems are designed for site specifications.

WHERE AND HOW IS IT COMMONLY USED? (SEE FIGURE DPS-8)

- On a stream of construction run off to treat the water prior to discharge

WHEN SHOULD IT BE INSTALLED?

- Before construction activities begin
- While construction activities are occurring
- To treat water stored on site
- To treat water when larger amounts of sediment load are present
- After project completion to treat dirty water stored on site
- In front of remediation equipment such as carbon filters, etc.
- When a very high quality effluent is required
- When precise dosing of treatment chemicals is required

WHEN SHOULD IT NOT BE INSTALLED?

- When power is not available
- If truck access to the area to service system is not possible

WHAT NEEDS TO BE INSPECTED?

- Is there excessive sediment loading in the storage structure?
- Are the chemical-feed pumps operating correctly?
- Do the chemical storage vessels have adequate product?
- Is the effluent water from the system of sufficient clarity?
- Does the water meet all effluent criteria?
- Does the residual water test show any remaining polymer in the effluent water?

WHAT MAINTENANCE ACTIVITIES CAN BE EXPECTED?

- Removal of sediment from the storage structure
- Maintaining operation of polymer feed pumps
- Changing of polymer storage vessels
- Maintenance of instrumentation
- Monitoring sand filter function to include changing of sand if needed.

NOTES

- Polymers in general should not be directly released into civic storm water systems or natural watercourses.
- Discharging water through vegetated areas or additional BMP's can further reduce turbidity.
- Filtrate can be collected for secondary treatment (optional).
- Biopolymers will completely degrade with enzymatic action.




Figure AIII-39: Liquid Dual Biopolymer (DPS): Active Treatment Model.

Semi-Passive Treatment of Turbid Water Utilizing a Liquid Dual Polymer System and Dewatering Bags

WHAT IS ITS PURPOSE?

To clean construction stormwater from a pond using a passive system prior to discharge into a regulated and/or high quality water body

WHERE AND HOW IS IT COMMONLY USED? (SEE FIGURE DPS-2)

- On a stream of construction run off to treat the water prior to discharge

WHEN SHOULD IT BE INSTALLED?

- When a high quality effluent is required
- Before construction activities begin
- While construction activities are occurring
- To treat water stored on site
- To treat water when larger amounts of sediment load are present
- After project completion to clean dirty water stored on site

WHEN SHOULD IT NOT BE INSTALLED?

- When power is not available
- If truck access to the area to deliver chemicals is not possible

WHAT NEEDS TO BE INSPECTED?

- Is there excessive sediment loading in the pond?
- Are the chemical-feed pumps operating correctly?
- Polymer dose rate jar testing for dose optimization (see chart below)
- Is the effluent water from the system of sufficient clarity?

WHAT MAINTENANCE ACTIVITIES CAN BE EXPECTED?

- Removal of sediment from the feed pond
- Maintaining operation of polymer feed pumps
- Maintaining sufficient quantity of polymer Changing of dewatering bag

NOTES

- Polymers in general should not be directly released into civic stormwater systems or natural watercourses.
- Discharging water through vegetated areas or additional BMP's can further reduce turbidity. Filtrate can be collected for secondary treatment (optional).
- Dewatering bags should be placed on rock, geotextile fabric or vegetative surfaces.
- Biopolymers will completely degrade with enzymatic action.




Figure AIII-40: Liquid Dual Biopolymer (DPS): with Multiple Dewatering Bags.

REFERENCES

1. Alabama Handbook, Practices for Erosion and Sediment Control, Chapter 9 (1993), "Anionic Polyacrylamide Erosion Control (PAM)"
2. Applied Polymer Systems, Inc., Acute and Chronic Toxicity Testing, MACTEC Engineering, 2003.
3. Applied Polymer Systems, Inc., Case History Data Base, Hydrograss Technologies Case File, South Hadley, MA Spring 2006a.
4. Applied Polymer Systems, Inc., Case History Data Base, Hydrograss Technologies Case File, Greenbush Corridor, MA Spring 2006b.
5. Brezonik, P.L. (1984). "Trophic State Indices: Rationale for Multivariate Approaches." In Lake and Reservoir Management, pp. 427-430, EPA-440/5-84-001.
6. Carter, O. C., Jr., Schiener, B.J. "Removal of Toxic Metals From and Industrial Wastewater Using Flocculants. Fluid/Particle Separation Journal. Vol. 4, No. 4. December 1991.
7. Chang, S.C., and Jackson, J.L. (1957). A Fractionation of Soil Phosphorus. *Soil Sci.*, 84, 133-144.
8. Chastain, J. P., Matias B. Vanotti, M. M. Wingfield. "Effectiveness of Liquid-Solid Separation for Treatment of Slushed Dairy Manure: A Case Study." Tektran. December 2000. USDA: Agricultural Research Service. 29 Jan. 2004.
9. Cooke, G.D., and Kennedy, R.H. (1981). Precipitation and Inactivation of Phosphorus as a Lake Restoration Technique. EPA-600/3-81-012.
10. Erwin, L, "Theory of Laminar Mixing" *Polym. Eng. Sci.* 18, 1044 (1978)
11. Flanagan, D. and Canady, N. (2006). "Use of Polyacrylamide in Simulated Land Application of Lagoon Effluent: Part II: Nutrient Loss, Transactions of the ASABE, 49(5): 1371-1381.
12. Garrison, P.J., and Knauer, D.J. (1984). "Long-Term Evaluation of Three Alum Treated Lakes." In Lake and Reservoir Management, pp. 513-517. EPA-440/5-84-001.
13. Georgia Soil Water Conservation Commission, Manual for Erosion and Sedimentation Control in Georgia, Fifth Edition, 2000.
14. Gowdy, W., Hanna, J. and Iwinski, S.R., (2006). "Technological Solutions for Erosion Control and Water Clarification using Polyacrylamide (PAM) and PAM Blends." Remediation Technology Symposium, Banff, Alberta, October 2006.
15. Green, Steven V and Stott D.E., Polyacrylamide: "A Review of the Use, Effectiveness, and Cost of a Soil Erosion Control Amendment", Selected papers from the 10th International Soil Conservation Organization Meeting held May 24-29, 1999 at Purdue University, Pages 384-389.
16. Harper, H.H. (December 1990). "Long-Term Performance Evaluation of the Alum Stormwater Treatment System at Lake Ella, Florida." Final Report submitted to the Florida Department of Environmental Regulation, Project WM339.
17. Iwinski, Steven R. "Erosion Control, Acid Rock Drainage Mitigation and Prevention Using PAM, a Co-Polymer of Polyacrylamide." Admiralty Island National Monument. Juneau, Alaska. May 1996.
18. Iwinski, Steven R., Stein, Ethan A., Condon, Peter D. "The Effects of Polymer on Metal Leaching in ARD Potential Rock." Admiralty Island National Monument. Juneau, Alaska. 29 Aug. 1996.
19. Iwinski, Steven R. "Treatment of Mine and Mill Water." Alaska Miners Association. 1995. Conference Juneau: Abstracts of Professional Papers. No. 18. Pg. 47. April 19-21. 1995.
20. Jernelov, A. (1970). Phosphate Reduction in Lakes by Precipitation with Aluminum Sulfate. 5th

International Water Pollution Research Conference. New York: Pergamon Press.

21. McLaughlin, R.A., Hayes, S.A., and Bartholomew, N., “Innovations (Old and New) for Improving Erosion, Sediment, and Turbidity Control”, 2003 International Erosion Control Association Meeting, Las Vegas, NV.
22. Orme S., and Kegley S., PAN Pesticide Data Base, Pesticide Action Network, North America, San Francisco, CA, 2004.
23. Price and Company, Inc., (Case File) Big Rock Point Restoration, Charlevoix, MI, Nov. 4, 2004.
24. Price and Company, Inc., (Case File) Oak Park Washtenaw Heights, Ann Arbor, MI, Feb. 3, 2005.
25. Sojka, R. E., Lentz, R. D., Bjornberg, D. J., Aase, J. K. “The PAMphlet.” Northwest Irrigation and Soils Research Lab. USDA: Agricultural Research Service. 26 Aug. 2003.
26. Virginia Erosion & Sediment Control Handbook, E&SC Technical Bulletin #2, “Application of Anionic Polyacrylamide for Soil Stabilization and Stormwater Management”
27. Yoon, Tae H., Hichung Moon, Yeong J. Park, Kyoung K. Pask. “Investigation of Metal Binding Sites on Soil Fulvic Acid Using Eu(III) Luminescence Spectroscopy.” Environmental Science Technology. 1994. Vol. 28. No. 12. Pg. 2139 – 2146. 1994.

APPENDIX IV
INSPECTION AND SCHEDULING FORMS

Site Name: _____ Date of Evaluation: _____ Page ____ of ____

Completed by: _____ Existing Weather Conditions: _____

Rainfall Event	Date Began	Duration (Hours)	Amount (Inches)	Rainfall Event	Date Began	Duration (Hours)	Amount (Inches)	Rainfall Event	Date Began	Duration (Hours)	Amount (Inches)
1				2				3			

SWPPP Information	YES	NO	N/A	Comments
	1. For a nonlinear project, is a sign or other notice: a) Posted conspicuously near the main entrance of the construction site or if not feasible, b) Posted in a local public building such as the town hall or public library For linear projects, is a sign or other notice posted at a publicly accessible location near the active construction project? √ Is a copy of the permit attached? √ Is the current location of the SWPPP and names and telephone numbers of a contact person for scheduling viewing times shown?			
2. Does a copy of the SWPPP and accompanying sediment and erosion control drawings exist on the construction site? √ Is the discharge permit on the construction site? √ Is the discharge permit acknowledgement letter on the construction site? √ Are the SWPPP and/or accompanying sediment and erosion control drawings updated and documented?				
3. Do inspection records exist on the construction sites? √ Has the frequency of inspections occurred as specified in the SWPPP? √ Have all previous inspection items been addressed and documented within seven (7) calendar days after an inspection?				
4. Do climatic records exist since the last inspection?				
BMP/Housekeeping Information				
5. Are offsite flows entering the construction site?				If yes, see attached detail report
6. Is there evidence of, or the potential for, increased pollutant (e.g., sediment, fuel, concrete waste, portable toilet waste, etc.) loading to enter the storm water conveyance system due to lack of maintenance or improper BMP installation?				If yes, see attached detail report
7. Do installation, repair and/or maintenance of <u>sediment</u> control BMPs need to occur?				If yes, see attached detail report
8. Do installation, repair and/or maintenance of <u>erosion</u> control BMPs need to occur?				If yes, see attached detail report
9. Is there evidence of sediment discharging <u>off</u> the construction site and onto downstream locations?				If yes, see attached detail report
10. Are vehicles tracking sediment <u>off</u> the construction site?				If yes, see attached detail report
11. If applicable, is soil, construction material, landscaping items, or other debris evident on the streets?				If yes, see attached detail report
12. Do locations exist where consideration of installing additional BMPs not found in the SWPPP should occur?				If yes, see attached detail report
13. Do locations exist where consideration of removing existing BMPs identified and shown in the SWPPP can occur?				If yes, see attached detail report
14. Does your site evaluation indicate a need to possibly update and document the SWPPP report and accompanying sediment and erosion control drawings within the next seven (7) days?				

Site Name: _____ Date of Evaluation: _____ Page ____ of ____

Completed by: _____

Detail Report: Identify the problem and its location. If appropriate, describe (in general terms) what needs to be done. However, only if qualified (e.g., you are a designer) should you be mandating specific BMPs to install.	Date done (with initials)
1.	
2.	
3.	
4.	
5.	
6.	
7.	
8.	
9.	
10.	

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

 (Print Name) (Signature) Date:

Title/Qualification of Inspector: _____

To be signed by a corporate officer **ONLY IF NO INCIDENTS** of non-compliance are found: I certify the construction site is in compliance with the SWPPP and any accompanying discharge permit(s) requirements:

 (Print Name) (Signature) Date:

PROJECT: _____ DATE: _____
 SCHEDULE FOR _____ AND _____ COMPLETED BY: _____

Indicate by use of a bar line or symbols when sediment and erosion control measures will be installed or when other activities will be implemented. Use additional forms as necessary.

MONTH																									
WEEK	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
OVERLOT GRADING																									
CONSTRUCTION ACTIVITIES																									
RAINFALL CONTROL																									
STRUCTURAL:																									
Sediment Containment System																									
Continuous Berm Barriers																									
Bale Barriers																									
Silt Fence Barriers																									
Rock Barriers																									
Inlet/Curb Barriers																									
Vehicle Tracking Pad																									
Terracing																									
NON-STRUCTURAL:																									
Permanent Seed Planting																									
Temporary Seed Planting																									
Mulching/Sealant																									
Sod Installation																									
Hillside RECPs																									
Channels RECPs																									
Asphalt/Concrete Paving																									
WIND CONTROL																									
Soil Roughening																									
Perimeter Barrier																									
Additional Barriers																									
Vegetative Methods																									
Soil Binders																									
WEED CONTROL																									
INSPECTION/MAINTENANCE																									

Comments:

PROJECT: _____ DATE: _____

COMPLETED BY: _____

SCHEDULE FOR _____ AND _____

Indicate by use of a bar line or symbols when sediment and erosion control measures will be installed or when other activities will be implemented. Use additional forms as necessary.

YEAR												
MONTH	1	2	3	4	5	6	7	8	9	10	11	12
OVERLOT GRADING												
CONSTRUCTION ACTIVITIES												
RAINFALL CONTROL												
STRUCTURAL:												
Sediment Containment System												
Continuous Berm Barriers												
Bale Barriers												
Silt Fence Barriers												
Rock Barriers												
Inlet/Curb Barriers												
Vehicle Tracking Pad												
Terracing												
NON-STRUCTURAL:												
Permanent Seed Planting												
Temporary Seed Planting												
Mulching/Sealant												
Sod Installation												
Hillside RECPs												
Channels RECPs												
Asphalt/Concrete Paving												
WIND CONTROL												
Soil Roughening												
Perimeter Barrier												
Additional Barriers												
Vegetative Methods												
Soil Sealant												
WEED CONTROL												
INSPECTION/MAINTENANCE												

This page intentionally blank

APPENDIX V
EXAMPLE PLANS AND DETAILS

PROJECT NAME
 SEDIMENT AND EROSION CONTROL PLAN
 PROJECT NO. xxxxxxxx
 TOWNSHIP, RANGE, SECTION NUMBER

USGS Quadrangle map here
 illustrating site location

1/4 Section, Township, Range
 Scale: 1" = 2000'

PRELIMINARY SCHEDULE

NO.	DATE	DESCRIPTION
1	10/15/13	PRELIMINARY SCHEDULE
2	10/15/13	PRELIMINARY SCHEDULE
3	10/15/13	PRELIMINARY SCHEDULE
4	10/15/13	PRELIMINARY SCHEDULE
5	10/15/13	PRELIMINARY SCHEDULE
6	10/15/13	PRELIMINARY SCHEDULE
7	10/15/13	PRELIMINARY SCHEDULE
8	10/15/13	PRELIMINARY SCHEDULE
9	10/15/13	PRELIMINARY SCHEDULE
10	10/15/13	PRELIMINARY SCHEDULE
11	10/15/13	PRELIMINARY SCHEDULE
12	10/15/13	PRELIMINARY SCHEDULE
13	10/15/13	PRELIMINARY SCHEDULE
14	10/15/13	PRELIMINARY SCHEDULE
15	10/15/13	PRELIMINARY SCHEDULE
16	10/15/13	PRELIMINARY SCHEDULE
17	10/15/13	PRELIMINARY SCHEDULE
18	10/15/13	PRELIMINARY SCHEDULE
19	10/15/13	PRELIMINARY SCHEDULE
20	10/15/13	PRELIMINARY SCHEDULE
21	10/15/13	PRELIMINARY SCHEDULE
22	10/15/13	PRELIMINARY SCHEDULE
23	10/15/13	PRELIMINARY SCHEDULE
24	10/15/13	PRELIMINARY SCHEDULE
25	10/15/13	PRELIMINARY SCHEDULE
26	10/15/13	PRELIMINARY SCHEDULE
27	10/15/13	PRELIMINARY SCHEDULE
28	10/15/13	PRELIMINARY SCHEDULE
29	10/15/13	PRELIMINARY SCHEDULE
30	10/15/13	PRELIMINARY SCHEDULE
31	10/15/13	PRELIMINARY SCHEDULE
32	10/15/13	PRELIMINARY SCHEDULE
33	10/15/13	PRELIMINARY SCHEDULE
34	10/15/13	PRELIMINARY SCHEDULE
35	10/15/13	PRELIMINARY SCHEDULE
36	10/15/13	PRELIMINARY SCHEDULE
37	10/15/13	PRELIMINARY SCHEDULE
38	10/15/13	PRELIMINARY SCHEDULE
39	10/15/13	PRELIMINARY SCHEDULE
40	10/15/13	PRELIMINARY SCHEDULE
41	10/15/13	PRELIMINARY SCHEDULE
42	10/15/13	PRELIMINARY SCHEDULE
43	10/15/13	PRELIMINARY SCHEDULE
44	10/15/13	PRELIMINARY SCHEDULE
45	10/15/13	PRELIMINARY SCHEDULE
46	10/15/13	PRELIMINARY SCHEDULE
47	10/15/13	PRELIMINARY SCHEDULE
48	10/15/13	PRELIMINARY SCHEDULE
49	10/15/13	PRELIMINARY SCHEDULE
50	10/15/13	PRELIMINARY SCHEDULE

- CONTRACTOR COMMITMENTS**
- The contractor commits to having a Designer complete at least biweekly inspections.
 - The contractor commits to conducting inspections at least once every seven (7) days and within 24 hours after a precipitation event of 0.50-inches or more.
 - The contractor commits to keeping copies of the construction site photographs and any modifications to the sediment and erosion control plans.
 - The contractor commits to completing necessary maintenance activities on BMPs within seven (7) days of an inspection.
 - The contractor commits to having one or more qualified technicians at the construction site at all times to be responsible for implementing, inspecting, and maintaining sediment and erosion control BMPs at all site areas requested or approved by the Designer.
 - The contractor commits to installing additional sediment and erosion control BMPs within seven (7) days after being recommended by the Designer.
 - If additional sediment and erosion control BMPs are recommended by the Designer, the contractor commits to completing all BMPs for the Designer regarding implementation of the additional BMPs.

1. A copy of the contractor's commitments for this project is attached to the permit application.

DESIGNER'S NOTE: THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE OF ALL BMPs AT ALL TIMES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE OF ALL BMPs AT ALL TIMES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE OF ALL BMPs AT ALL TIMES.

INDEX



- PRE- & DURING CONSTRUCTION SEDIMENT CONTROL PLAN
- AFTER CONSTRUCTION (A.K.A. EROSION CONTROL) PLAN
- TYPICAL DETAILS
- SPECIFICATIONS

U.S. APPROVED
 DESIGN NUMBER

PROJECT NAME
 SEDIMENT AND EROSION CONTROL PLAN
 EXAMPLE TITLE PAGE

- Prior to construction activities:
 - Install silt fence or continuous berm barrier along the creek (See details S1 and S9).
 - Where access points to the stream are present, create a sediment containment area with the continuous berm or rock barrier (See details S1 and S9).
- As required by the Designer or Engineer, complete the following upstream of culvert:
 - Excavate a 20"-to-36"-deep trench about 15'-to-20' wide and 12" to 18" deep and place a rock barrier in front of the opening (See detail S9).
 - Disturbed lands with final grades will not remain unprotected against erosion for more than 14 days (See After Construction drawings).
- The maximum lift height of fill material without erosion protection must not exceed 30'-ft.
- After every runoff event, inspect and maintain all systems.
- Continually inspect out and fill slopes for erosion and sediment. Immediately implement mitigation measures upon approval by the Designer or Engineer.
- Where illustrated, maintain 6"-to- or higher berm along the edge of fill material to divert runoff into a slope drain (See details S7 and S8).
- Revisions to this sediment and erosion control plan must be approved by the Designer or Engineer.
- This plan is subject to change by the Designer or Engineer.

- 212-010A SEDIMENT TRAP
1 EACH STA 179+35 LL
- 212-011A SILT FENCE
300 FT STA 178+00 - 174+00 RL
140 FT STA 175+00 - 170+00 LL
- 212-020A TO BE MAINTAINED AS FILL MATERIAL IS PLACED
- 212-020A STONE FILTER DAM TYPE 1
3 cu. yds. STA 178+40 LL
- 212-020A TUFF REINFORCEMENT MAT (TRM)
25 sq. yds. STA 172+40 LL
10 sq. yds. STA 170+40 LL



IMMEDIATELY AFTER INSTALLING THE CULVERT, COMPLETE WHAT IS REQUIRED BY NOTE NO. 2

INSTALL A SEDIMENT TRAP SYSTEM UPSTREAM OF THE CULVERT PRIOR TO PLACEMENT OF FILL MATERIAL.

DISCHARGE CHANNEL DOWN FILL MATERIAL SHALL BE PROTECTED BY A TRM (SEE DETAIL S4)


AS EACH LIFT OF FILL MATERIAL IS PLACED, MAINTAIN A 12-IN. HIGH EARTHEN DIVERSION CHANNEL TO DIVERT RUNOFF

DISCHARGE CHANNEL ON FILL MATERIAL SHALL BE PROTECTED BY A TRM (SEE DETAIL S4)


AVOID BLOCKING DISCHARGE END OF CULVERT WITH SILT FENCE


INSTALL SILT FENCE BARRIER ALONG FAR EDGE OF CONSTRUCTION AREA OR R.O.W. BEFORE BEGINNING EXCAVATION ACTIVITIES

DEVELOP A 12-IN. EARTHEN DIVERSION CHANNEL TO PROTECT ROADWAY



<p>FLORIDA DEPARTMENT OF TRANSPORTATION</p> <p>ROADWAY 205E PRE- AND DURING CONSTRUCTION E&SC PLANS Station 170+00 to 176+00</p>	
<p>DESIGNED BY: _____</p> <p>DRAWN BY: _____</p> <p>CHECKED BY: _____</p> <p>DATE: _____</p>	<p>SCALE: 1" = 20'</p>





1. Sediment control structures (e.g. silt fences, rock barriers, etc.) will be removed as instructed by the Designer or Engineer.
2. Unless advised differently by the Designer or Engineer, sediment traps will remain in place as illustrated.
3. Before planting seed or installing sod, apply topsoil to a thickness of at least 6-in.
4. Planting of seed may occur by use a drill or by broadcast methods.
5. Within 24 hours after planting seed, one or more of the following approved slope protection methods will be installed:
 - Rolled Erosion Control Products (RECPs), or
 - Straw-Coconut ECB applied wood fiber mulch at a rate of at least 1.5 tons/ac, or
 - Straw mulch applied at a rate of at least 2.0 tons/ac. and held in place with an approved tackifier.
6. Unless advised differently by the Designer or Engineer, RECPs will be installed where illustrated.
7. Modifications to this erosion control plan must receive approval by the Designer or Engineer.
8. This erosion control plan is subject to variations by the Designer or Engineer.

612-005A DIVERSION CHANNEL
30 ft. STA. 176+70 - 176+00 RL

611-005A STRAW-COCONUT ECB
30 sq. yds. STA. 176+70 - 176+00 LL

611-005B EROSION CONTROL MAT (ECM)
215 sq. yds. STA. 170+00 - 172+48 LL
60 sq. yds. STA. 174+00 LL - 175+00 RL
106 sq. yds. STA. 174+00 - 175+00 RL

611-005C LOGS RIPRAP
3 sq. yds. STA. 175+75 RL

Flank seed and apply mulch or RECPs

Plant seed and apply mulch or RECPs OR install sod

Install sod

Sediment Trap

Slope Brk

Riprap

Flow Direction


Pay Item

REB = Rolled Erosion Control Blanket
RECP = Rolled Erosion Control Product

ROADWAY 205E
AFTER CONSTRUCTION E&SC PLANS
Station 170+00 to 176+00




NO.	DATE	BY	REVISIONS	DESCRIPTION



ROADWAY 205E
PRE- AND DURING CONSTRUCTION E&SC PLANS
Station 176+00 to 182+00



NO.	DATE	BY	REVISIONS	DESCRIPTION	DESIGNED	CHECKED	DATE	DESIGNED	DATE	DESIGNED	DATE



ROADWAY 205E
Roadway Profile
Station 1760+00 to 182+00



DESIGNER: _____
DATE: _____


DESIGNED: _____
DESIGNED CHECKED: _____
DATE: _____

REVISIONS

NO.	DATE	BY	DESCRIPTION

DESIGNED CHECKED: _____
DATE: _____
DRAWING CHECKED: _____
DRAWING DATE: _____

SHEET _____ OF _____



- Sediment control structures (e.g., silt fences, brush berms, etc.) shall be installed and maintained by the Designer or Engineer.
- Unless advised differently by the Designer, riprap structures will remain in place as illustrated.
- Before placing seed or installing mat, apply topsoil to a thickness of at least 6-in.
- Planting of seed may occur by use of a drill or by broadcast methods.
- Within 24 hours after planting seed, one or more of the following erosion control protection methods will be installed:
 - Roll-on Erosion Control Products (ECPM), or
 - Hydraulically applied wood fiber mulch at a rate of at least 1.6 tons/600 sq. yds.
 - Straw-coconut matting at a rate of at least 2.0 tons/600 sq. yds. with an approved tackifier.
- Unless advised differently by the Designer or Engineer, ECPM's will be installed where illustrated.
- Modifications to this erosion control plan must receive approval by the Designer or Engineer.
- This erosion control plan is subject to revisions by the Designer or Engineer.

EROSION CONTROL PROTECTIVE MAT (ECPM) 240 sq. yds. STA 176+00 - 178+50 RL	STRAW-COCOON ECB 500 sq. yds. STA 176+00 - 177+50 RL 500 sq. yds. STA 178+00 - 178+50 RL 500 sq. yds. STA 179+00 - 180+00 RL 500 sq. yds. STA 180+00 - 181+00 RL 500 sq. yds. STA 181+00 - 182+00 RL	TRIP REINFORCEMENT MAT (TRM) 70 sq. yds. STA 176+00 - 176+00 LL
LONGER RIPRAP 3 sq. yds. STA 178+81 RL 3 sq. yds. STA 178+81 RL 3 sq. yds. STA 180+70 RL		

Plant seed and apply mulch or ECPM's

Plant seed and apply mulch or ECPM's OR manual seed

Install seed

Sediment Trap

Slope Berm

Regravel


Flow Direction

Existing Fence


Pay Item

ECB = Erosion Control Blanket
TRM = Trip Reinforcement Mat
ECPM = Erosion Control Protective

SHEET _____ OF _____



- NOTES FOR THE ABOVE BMPS**
1. REMOVE ACCUMULATED SEDIMENT FROM BEHIND ROCK BARRIERS WHEN IT IS WITHIN 6-IN. OF THE TOP OF THE ROCK.
 2. REMOVE ACCUMULATED SEDIMENT FROM BEHIND THE SILT FENCE WHEN IT IS OVER 24-IN. DEEP.
 3. REMOVE ROCK BARRIER, POSTS, AND WIRE ONCE EROSION CONTROL PRACTICES ARE INSTALLED.
 4. REMOVE SILT FENCE FABRIC AND POSTS ONCE EROSION CONTROL PRACTICES ARE INSTALLED.





- REQUIRED FOR ALL INSTALLED BMPS**
1. AT LEAST EVERY 7 DAYS DURING THE RAINFALL SEASON, INSPECT AND REPAIR ANY DAMAGE FOUND.
 2. WITHIN 24 HOURS AFTER RUNOFF EVENTS, INSPECT AND REPAIR ANY DAMAGE FOUND.
 3. AT LEAST EVERY 30 DAYS DURING THE WINTER MONTHS, INSPECT AND REPAIR ANY DAMAGE FOUND.

NO.	DATE	BY	REVISIONS	DESCRIPTION	DESIGNED	CHECKED	DATE

FLORIDA DEPARTMENT OF TRANSPORTATION

SHEET _____ OF _____





SILT FENCE BARRIER INSTALLATION

TRENCHING METHOD
 FABRIC MATERIAL LAYERS BE 4'-6" WIDE AND 10'-0" LONG. TRENCH WITH A 2" DEEP, 4" WIDE V-GROOVE. BACKFILL WITH 2" GRANULAR MATERIAL. FABRIC MATERIAL LAYERS BE 4'-6" WIDE AND 10'-0" LONG. TRENCH WITH A 2" DEEP, 4" WIDE V-GROOVE. BACKFILL WITH 2" GRANULAR MATERIAL.

SLICING METHOD
 ATTACHMENTS THRU SILT FENCES WHEN TRENCHING IS USED. FABRIC MATERIAL LAYERS BE 4'-6" WIDE AND 10'-0" LONG. TRENCH WITH A 2" DEEP, 4" WIDE V-GROOVE. BACKFILL WITH 2" GRANULAR MATERIAL.

ROCK BARRIER OUTLET STRUCTURE FOR CULVERTS

TOP VIEW
 ROCK BARRIER MUST BE SPREAD AT LEAST 10'-0" FROM THE END OF THE CULVERT. INSTALLING WITH ROCK TRENCHER.

FRONT VIEW
 HORIZONTAL SPACING BETWEEN ROCK POINTS SHALL NOT EXCEED 5'-0".

SIDE VIEW
 ROCK BARRIER MUST HAVE A MINIMUM WIDTH OF 24"-36". SUPPORTS MUST BE SPACED TO MATCH POINTS.

SOIL TRACKING PREVENTION DEVICE

SIDE VIEW (INT)
 36"-FT. MINIMUM WIDTH. 18"-FT. MINIMUM HEIGHT. 18"-FT. MINIMUM LENGTH.

PLAN VIEW (INT)
 36"-FT. MINIMUM WIDTH. 18"-FT. MINIMUM LENGTH.

SECTION A-A (INT)
 36"-FT. MINIMUM WIDTH. 18"-FT. MINIMUM LENGTH.

SEDIMENT CONTAINMENT SYSTEM FAIRCLOTH® SURFACE SKIMMER

TOP VIEW
 FABRIC MATERIAL LAYERS BE 4'-6" WIDE AND 10'-0" LONG. TRENCH WITH A 2" DEEP, 4" WIDE V-GROOVE. BACKFILL WITH 2" GRANULAR MATERIAL.

END VIEW
 FABRIC MATERIAL LAYERS BE 4'-6" WIDE AND 10'-0" LONG. TRENCH WITH A 2" DEEP, 4" WIDE V-GROOVE. BACKFILL WITH 2" GRANULAR MATERIAL.

CURB AND GUTTER SEDIMENT CONTAINMENT SYSTEM

PLACE TWO OR MORE SETS OF SAND BAGS IN A MANNER THAT RESULTS IN MAXIMUM SUPPORT. THE FLOW LINE BAG MUST BE LOWER THAN THE TOP OF THE CURB.

STREET GRADE (FT)	FLOOD SPACING (FT)
1.0	50
2.0	25
3.0	16
4.0	13
5.0	10

NOTE: FILL SAND BAGS ABOUT 2/3 FULL BEFORE PLACING IN THE GUTTER.

INSTALLING A DISTURBED SLOPE RECP

RECP SHALL BE INSTALLED WITH A MINIMUM OF 3" SAND. RECP SHALL BE 3'-0" WIDE AND 18"-FT. HIGH. RECP SHALL BE 18"-FT. LONG. RECP SHALL BE 18"-FT. HIGH. RECP SHALL BE 18"-FT. LONG.

INSPECTION REQUIREMENTS FOR ALL INSTALLED BMPS

- AT LEAST ONCE EVERY 7 DAYS, INSPECT AND REPAIR ANY DAMAGE FOUND.
- REPAIR ANY DAMAGE FOUND.

RESIDENTIAL AND COMMERCIAL TYPICAL DETAILS PAGE 2

AV-11